

# Road Maintenance (C) Infrastructure Tour (Technical exchange)

Kochi Interchange Line ▪ Southern East Road ▪ Oroku Road

Explanation of the inspection site

Nov. 13–14, 2025


Okinawa Professional Engineers' Association


# Inspection Site Location Map

①Kochi Interchange Line

②Southern East Road

③Oroku Road






# Explanation of the inspection site

Project Name	Kōchi Interchange Line	Southern East Road	Oroku Road
Site Visit Day	Thursday, November 13, afternoon	Friday, November 14, morning	Friday, November 14th, afternoon
Business entity	Okinawa Prefecture, West Nippon Expressway Company Limited	Okinawa Prefecture	Okinawa General Bureau, Cabinet Office Southern National Highway Office
Major roads, etc.	Okinawa Expressway	Regional High-Standard Road South-East Route (Haebaru Chinen Line)	Naha Airport Expressway
Place	Kōchi, Urasoe City (Kōchi Interchange Construction Site Office)	Oozato, Nanjo City (South East Road Construction Site Office)	Oroku, Naha City (Naha Airport Expressway Branch Office)
Travel time	About a 10-minute drive	About 40 minutes by car	About 45 minutes by car
Purpose	<ul style="list-style-type: none"> <li>• Traffic congestion relief: Expected to improve traffic conditions in the surrounding area.</li> <li>• Regional revitalization: Contributes to the revitalization of the surrounding community.</li> </ul>	<ul style="list-style-type: none"> <li>• It is a road that ensures regular hours and speeds, aims to establish a 30-minute area to Naha City, provides urban services to local residents, and supports the development of the southern region.</li> <li>• It is expected to promote tourism, support medical services, encourage industrial development, and improve the roadside environment.</li> </ul>	<ul style="list-style-type: none"> <li>• Ensure regular and high-speed service between the northern and central-southern parts of Okinawa Island and Naha Airport.</li> <li>• Alleviate traffic congestion in the Oroku area along National Route 331.</li> <li>• Support efficiency in logistics and tourism on Okinawa Island.</li> </ul>
Business Extension	約0.8km	7.4km 約2.0km（暫定開通）2022年3月	5.7km
Construction period	Fiscal Year 2018～	Fiscal Year 2015～	Fiscal Year 2014～
Progress rate	Construction Office・Confirmation on Site	Construction Office・Confirmation on Site	Construction Office・Confirmation on Site
Site visit	Bridge (superstructure), Cut slope construction, Ground improvement work, etc.	Environmental countermeasures sites, etc.	OFF lamp bridge upper part, Bridge upper part (P15-P19), Bridge upper part (P19-P24)

# Kochi Interchange Line Interchange

Expected Completion Drawing





# 3D・VRシミュレーションコンテスト FORUM8

<https://vrcon.forum8.co.jp/2023/>




ノミネート賞

金秀建設株式会社


幸地インター線橋梁整備工事（Dランプ上部工）

2分20秒/4分33秒





# Kōchi Interchange Line Construction Status (From Central to Terminal Side) Photographed August 2025







## Each construction project and related technologies

Construction Name	Project Name	Construction Method	Construction Progress	Related Technologies
Bridge construction	Foundation work	Pile Foundation (Cast-in-Place Pile Method)	Construction completed	① Red soil runoff countermeasures, environmental conservation
	Substructure work	Abutment and Pier Construction (Concrete Work)	Construction completed	② Salt Damage Countermeasures, Infrastructure Longevity Enhancement
	Superstructure Work (D Ramp Overpass)	Bent method: Factory fabrication and on-site erection (550-ton crane)	Construction completed	② Salt Damage Countermeasures, Infrastructure Longevity Enhancement
	Superstructure Work (A, B, D Ramp Bridges)	Fixed Formwork Installation Concrete Work	Construction completed	② Salt Damage Countermeasures, Infrastructure Longevity Enhancement ⑥ ICT Utilization
Cutting work	Cut slope construction	Steel Bar Insertion Work Retaining pile work	Construction completed	④ Disaster Prevention Measures
Earthwork construction	Ground improvement work	Mid-layer mixing treatment method	Under construction	① Red soil runoff countermeasures, environmental conservation
	Earthwork construction	高盛土工事	Future construction	① Red soil runoff countermeasures, environmental conservation



# Bridge Construction Bridge Types and Substructures

Bridge Name	Bridge length (m)	Effective width (m)	Bridge Types	Lower form	Foundation work type	Year of Completion
A Lamp Bridge	89.5	6.01	Post-tensioned PC3 span Continuous cast-in-place hollow slab bridge	Inverted T-shaped abutment Wall-type pier	cast-in-place pile $\phi 1500$	2025.5
B Lamp Bridge	68.6	6.01	Post-tensioned PC3 span Continuous cast-in-place hollow slab bridge	Inverted T-shaped abutment Wall-type pier	cast-in-place pile $\phi 1500$	2025.5
B Ramp Bridge No. 2	32.0	6.01	Post-tensioned PC Simple Cast-in-place Hollow Deck Bridge	Inverted T-shaped abutment Wall-type pier	cast-in-place pile $\phi 1500$	2025.2
D Lamp Bridge	79.4	12.01	Post-tensioned PC3 span Continuous cast-in-place hollow slab bridge	Inverted T-shaped abutment 張出壁式橋脚	cast-in-place pile $\phi 1500$	2023.12
D Lamp Overpass	62.0	12.01	Steel Simple Composite Narrow-Flange Box Girder Bridge	Inverted T-shaped abutment	cast-in-place pile $\phi 1500$	2023.3





# Bridge construction (Foundation Works・Lower Structure Works)

Photographed in June 2023





# Bridge construction, substructure construction and A · D ramp substructure A2



Surveying work



Installation of construction signs, etc.



Excavation




Magnetic exploration  
(stratigraphic exploration)

(Overall construction flow chart) Source: Nakamoto Kogyo Co., Ltd.



# Bridge construction, substructure construction and A · D ramp substructure A2



(Overall construction flow chart)



Excavation machine installation  
(full rotary machine installation)



Drilling status




Installing the steel cage and spacers



Pile head treatment construction



# Bridge construction, substructure construction and A · D ramp substructure A2



(Overall construction flow chart )



Foundation installation



Pouring smooth concrete




Bottom plate rebar assembly



Bottom slab formwork assembly



# Bridge construction, substructure construction and A · D ramp substructure A2



(Overall construction flow chart )



Pouring concrete for base plate



Spreading concrete curing material




Pouring of base concrete completed



Formwork removal



# Bridge construction, substructure construction and A · D ramp substructure A2



(Overall construction flow chart)



Assembling vertical wall rebar (1st lot)



Assembling vertical formwork (1st lot)




Pouring concrete (1st lot)



Spraying treatment material for vertical wall concrete joints



# Bridge construction, substructure construction and A · D ramp substructure A2



(Overall construction flow chart )



Backfill



Scaffolding assembly




Pouring concrete for vertical walls (2nd lot)




Vertical wall concrete pouring (3rd lot)



# Bridge construction, substructure construction and A · D ramp substructure A2



(Overall construction flow chart )



Vertical wall rebar assembly (3rd lot)



Vertical formwork assembly (3rd lot)




Pouring concrete for vertical walls (3rd lot)



Vertical wall concrete pouring completed



# Bridge construction, substructure construction and A · D ramp substructure A2



(Overall construction flow chart )



Dismantling scaffolding



Backfilling



Bridge abutment completed



Bridge abutment completed



## Bridge Construction (Superstructure) D Ramp (Overpass) Photographed June 2023






# Bridge Construction Superstructure Work D Ramp (Overpass) Steel Superstructure

## ① Factory Production

- Material Receiving
- NC Cutting
- Major Assembly
- Ultrasonic Testing
- Pre-Assembly Inspection
- Factory Painting
- Film Thickness Measurement
- Transportation (Sea/Land)





## ② Site Erection

- Vent installation
- Ground-level girder erection (2B) span between Bent and A2160-ton crane
- 550-ton crane assembly
- Large Block Installation (2B) A1 to Vent
- 550-ton crane dismantling
- 合成床版架設
- Reinforcement assembly
- Concrete placement

# ① Factory production

工場製作フローチャート



材料入荷



NC切断



大組立



超音波探傷試験



# ① Factory production


工場製作フローチャート



# Bridge Construction Superstructure Work D Ramp (Overpass) Steel Superstructure

## ① Factory Production

- Material Receiving
- NC Cutting
- Major Assembly
- Ultrasonic Testing
- Pre-Assembly Inspection
- Factory Painting
- Film Thickness Measurement
- Transportation (Sea/Land)



## ② Site Erection

- Vent installation
- Ground-level girder erection (2B) span between Bent and A2160-ton crane
- 550-ton crane assembly
- Large Block Installation (2B) A1 to Vent
- 550-ton crane dismantling
- 合成床版架設
- Reinforcement assembly
- Concrete placement





## ② On-site installation

ベント設備設置
ベント基礎設置
ベント設置状況
ベント設置完了
ベント変位計測

### 外側線撤去・仮設置

鋼橋架設（ベント～A2間）
160t吊クレーン組立
地組桁架設（2B）
横桁取付
地組桁架設（1B）
横桁取付
架設完了
160t吊クレーン解体

鋼橋架設（A1～ベント間）
550t吊クレーン組立
試験吊り
大ブロック架設（2B）
横桁取付
大ブロック架設（1B）
横桁取付
架設完了
550t吊クレーン解体



550t lifting crane assembly



550t lifting crane assembly Large block erection (2B) between A1 and vent



架設完了



550t吊クレーン解体



② On-site installation



合成床版架設完了



鉄筋組立完了



打設状況



打設完了



# Bridge construction: Superstructure construction (D ramp)


Photographed in June 2023






# D ramp bridge


ポストテンション方式PC3径間  
連続場所打ち中空床版橋



**Dランプ橋 橋梁一般図**




# Bridge construction: Superstructure construction (D ramp)



7-2 Temporary works (lifting equipment A1)



7-3 Rubber bearing construction



7-4 Shoring foundation




7-5-1 Formwork assembly

Source: Kanehide Construction Co., Ltd. and  
Okinawa PC Co., Ltd. JV



# Bridge construction: Superstructure construction (D ramp)




Source: Kanehide Construction Co., Ltd. and  
Okinawa PC Co., Ltd. JV




7-5-2 Reinforcing bar assembly (lower bar)



7-5-3 PC cable sheath (overall view)




7-5-1 Formwork assembly (cylindrical formwork)



7-5-2 Reinforcing bar assembly (upper bar)





7-5-4 Concrete pouring



7-5-5 Cable tensioning



7-5-5 Ground injection



Completed (view of A1-A2)



## Bridge construction: Superstructure construction (D ramp)

Video  
explanation

2 minutes 27  
seconds



幸地インター線橋梁整備工事 (Dランプ上部工)



金秀建設株式会社土木工部  
チャンネル登録者数 1 人

チャンネル登録

👍 1



🔗 共有

📶 オフライン

🔖 保存



138 回視聴 11 か月前

<https://www.youtube.com/watch?v=sNs2BLETdRs>

2 minutes 27 seconds - **Kochi Interchange Line Bridge Construction Work (D Ramp Superstructure) - Some voice explanations**



## Cut-slope construction





## Cut-slope construction

### Reinforcing Bar Insertion Work


- Tree Removal
- Red Soil Erosion Prevention Measures
- Magnetic Survey
- Slope Shaping
- Borehole Angle Verification and Drilling
- Reinforcement Bar Insertion Status
- Torque Wrench Tightening Verification

### Restraint Pile Method

- Scaffolding erection
- やぐら組立
- Excavation (large-diameter boring work)
- Pile installation
- Mortar placement
- Scaffolding and tower removal
- Head connection



## Landslide Investigation and Design Review Flow




**Landslide Countermeasures: Reinforced Concrete Piles, Retaining Piles**



# Cut-slope construction



# Rebar Insertion Work



Upon completion





1-5 伐採



1-6 赤土流出防止対策



1-2 法面整形



1-3 削孔角度確認・削孔



1-4 補強筋挿入状況



1-8 トルクソ締付け確認






# Ground Improvement Work / Embankment Construction





# Design plan



Ground improvement  
construction  
ICT earthwork  
(GNSS)

着手前



A1橋台（真上より）

完成



A1橋台（真上より）



A2橋台（真上より）



A2橋台（真上より）



# Ground improvement construction

A1架設ヤード準備工

準備工

基本測量・事前調査

調査ボーリング

A1架設ヤード事業損

確認探査掘削

地盤改良工

プラント組立

プラント機材搬入



基本測量



調査ボーリング




探査状況



地盤改良プラント設置完了



# Ground improvement construction



GNSS測位アンテナ取付



本攪拌改良（深度及び圧力モニター確認）



ICT施工（光波による位置確認）②点目



チームピュアによるリモート確認状況